

SOLID SURFACE FABRICATION

CORIAN GENERAL CONDITIONS

1. All appliances, sinks, faucets, and additional cutouts must be on the job at the time of installations. A return trip to complete will be charged at an hourly rate.
2. If template cannot be completed at the requested time, a \$75.00 charge will be added for the return trip.
3. Cabinets must be level. If we are to level, an hourly charge will be assessed.
4. In the case of a countertop replacement job (remodel or upgrade), tear-out removal from job site, plumbing, and electrical hookups are not included in countertop pricing. We will require a signed tear-out form before we start the project.
5. Customer is responsible for patching walls after tear-out of old countertops, backsplash or wall splash (i.e. laminate).
6. Countertop will be fabricated to a matte finish for easy homeowner maintenance.
7. Due to the grain effect in the DuPont Corian Private Collection Series and Venaro Series colors, a seam may be noticeable in the corners of "L" and "U" shaped tops.
8. Due to particulate distribution in all solid surface patterned colors, some edge details may show a layer striating effect.
9. When combining same color solid surface bowls and sheets, there may be a noticeable variation in color.
10. All cutouts from sinks and cook tops are the property of McGrory, Inc. The owner will receive one (1) cutting board with each kitchen installation.
11. Wall Material-If scored Wall Material is requested, we require a complete dimensional drawing showing details. We cannot be responsible for the final layout with your customer.
12. Special details, i.e., stripes, inlays, and drain boards must be fully dimensioned on your drawing.
13. Wall material on a cove backsplash will be a silicone joint.
14. Space between backsplash and walls or any paintable surface will not be caulked.
15. Undermount kitchen sinks by other manufacturers should include additional support, supplied by you, to prevent the sink from coming loose, especially if there is a garbage disposal. We require the bowl at the time of template.
16. When using a cove backsplash, please remember that the cove is perfectly straight, we cannot scribe this detail.
17. Maximum overhang on a kitchen countertop is 8" for ½" deck with buildup with maximum run of 6 feet before a bracket is required. If your overhang is larger, is in a heavy use area, or is near a cutout, please allow for brackets or other supports.
18. Underside of overhang on ledges and islands is finished with unpainted MDF unless otherwise noted.
19. If bowl is by others, our price includes cut-out for bowl.
20. Joint between countertop and backsplash will be a silicone joint. This is for standard height backsplash and wall work